CHITALDRUG DISTRICT.

Notification dated 28th March 1936.

The undermentioned 5 (five) license books each book containing 1 to 50 pages in triplicate supplied to the Amildar, Chellakere Taluk, during the year 1922 as noted against each License Book are reported to be missing in the Taluk Office, Chellakere.

Notice is therefore hereby given that the said books if found at any time by anybody, should be promptly presented to the District Forest Officer, Chitaldrug as they are.

The Public are hereby cautioned against obtaining any licenses from out of these books and also against their unauthorised use. Persons in possession of these licenses in any manner being held liable to prosecution under the rules.

M F. P. License Books Nos. 505, 507, 510, 511 and 512—5 books.

D. NARASIMHAMURTI RAO,
District Forest Officer.

ENGINEERING DEPARTMENT

BUILDINGS DIVISION, BANGALORE.

Abstract Notification dated 6th April 1936.

The attention of the public is invited to the notification calling for tenders for constructing quarters for Sub-Assistant Surgeon and Matrons quarters attached to the Bangalore Central Jail in Jail Extension, Bangalore, published on pages 495 to 497, of Part VI of the *Mysore Gazette*, dated 9th April 1936.

The last date of receiving tenders is 23rd April 1936.

N. KRISHNA IYENGAR,
Executive Engineer.

BANGALORE DIVISION.

Notification dated 11th April 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M. on 25th April 1936 for improving Rampur Ananthankatte tank, Registered No. 274 of Dodballapur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1936.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred (Rs. 200) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Improving Rampur Ananthankette tank, Registered No. 274 of Dodballapur Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Approximate quantities required for improving Rampur Ananthankatte Tank, Registered No. 274 of Dodballapur Taluk.

No.	Items of work	Unit	Quantity	Rate sanctioned	Rate quoted in Figures	Rate quoted in Words
				Rs. a. p.		
	Bund.					
1	Removing anthill and filling in sand ..	Each	4	1 0 0		
2	Cutting central trench at top and grips on slopes of bund	Grade	12	3 0 0		
3	Earthwork to bund with lead and lift including watering and tamping ..	C.yd.	6,043	0 3 6		
4	Turfing the slopes of bund and watering till it is satisfactory	S.yd.	4,904	0 0 9		
5	Removing and resetting rough stone revetment old with ½ new stones and jelly required	C.yd.	200	0 12 0		
6	Rough stone work new with jelly backing	,,	615	1 8 0		
7	Gravel backing to new stone work ..	,,	205	0 8 0		
8	Providing and fixing new grade stones with bed slabs including figures chistled and painted	Each	19	1 8 0		
9	Do date and register No. stone do	,,	1	3 0 0		
10	Do gauge stone do ..	,,	1	15 0 0		
11	Do B. M. stones do ..	,,	2	3 0 0		
12	Do Index stones	,,	19	0 8 0		
	Sluice.					
1	Providing wooden plug and rod with locking arrangements, etc. ..	Each	1	14 0 0		
2	Burnt brick in surki mortar ..	C.ft.	20	0 5 0		
3	Surki mortar plastering	Sqr.	5·00	4 0 0		
	Waste Weir.					
1	Removing old stones	C.yd.	5	0 8 0		
2	Earthwork clearing site	,,	70	0 4 0		
3	Do excavating foundation ..	,,	49	0 4 0		
4	Burnt stone jelly concrete in surki mortar	C.ft.	119	0 4 0		
5	Burnt brick in surki mortar ..	,,	434	0 5 0		
6	Plastering with surki mortar ..	S.ft.	5·13	4 0 0		
7	Burnt stone slabs 6″ thick dressed and fixed in surki mortar	S.ft.	167	0 6 0		
8	Rough stone work new	C.yd.	45	1 8 0		
9	Cutting joggle joints	Each	11	1 0 0		
10	Earthwork clearing draft and approach and using the earth for training bank	C.yd.	387	0 4 0		

Notification, dated 9th April 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M. on 25th April 1936 for restoring Chikkondahalli Chikkere, Registered No. 113 of Hoskote Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of August 1936.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. and 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred and fifty in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Chikkondhalli Chikkere, Registered No. 113 of Hoskote Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Approximate quantities required for restoring Chikkondahalli Chikkere Minor Tank, Registered No. 113 of Hoskote Taluk.

No.	Items of work	Unit	Quantity	Rate sanctioned	Rates quoted in	
					Figures	Words
	Bund.			Rs. a. p.		
1	Cutting grips and trenches	Grade	21	3 0 0		
2	Earthwork to bund with lead and lift including watering and tamping ..	C.yd.	4,299	0 3 6		
3	Turfing the slopes of bund and watering till it is satisfactory	S.yd.	3,551	0 0 10		
4	Removing and resetting old stone work with new jelly	C.yd.	26	0 12 0		
5	Rough stone work new	,,	348	1 10 0		
6	Providing and fixing new grade sotnes with bed slabs including figures chiseled and painted	Each	22	1 8 0		
7	Do register and date stones do ..	,,	1	2 8 0		
8	Do B.M. stones do ..	,,	2	1 8 0		
9	Do Gauge stones	,,	1	12 0 0		
10	Do Index stones	,,	22	0 6 0		

No.	Items of work	Unit	Quantity	Rate sanctioned	Rates quoted in	
					Figures	Words
	Sluice.			Rs. a. p.		
1	Earthwork cut opening the bund ..	C.yd.	62	0 3 6		
2	Do excavating foundation ..	,,	10	0 3 0		
3	Stone jelly concrete in surki mortar ..	C.ft.	200	0 4 0		
4	Burnt brick in surki mortar ..	,,	193	0 5 0		
5	Burnt stone slabs 6″ thick dressed and fixed in surki mortar	S.ft.	127	0 6 0		
6	Plastering with surki mortar ..	Sqr.	21.7	3 12 0		
7	Cutting holes in slabs	Each	4	1 0 0		
8	Providing teak wood plug with iron rods and locking arrangements ..	,,	1	15 0 0		
9	Carting and fixing 6″ dia. C.I. pipes; pipes will be supplied departmentally at Bangalore	R.ft.	18	..		
10	Earthwork refilling with consolidation.	C.yd.	35	0 2 6		
	Weir.					
1	Earthwork excavation	C.yd.	45	0 3 0		
2	Stone jelly concrete in surki mortar ..	C.ft.	188	0 4 0		
3	Burnt stone in surki mortar ..	,,	241	0 5 0		
4	Burnt stone slabs 6″ thick dressed and fixed in surki mortar	S.ft.	116	0 6 0		
5	Pointing with cement mortar ..	Sqr.	3.48	3 6 0		
6	Rough stone work new	C.yd.	28	1 10 0		
7	Cutting joggle joints	Each	7	0 12 0		
8	Earthwork draft and approach clearing and used to training bank ..	C.yd.	378	0 3 6		

Notification dated 10th April 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M. on 25th April 1936 for restoring and improving Kambliganahalli Agraharadakere, Minor Tank, Registered No. 15 of Hoskote Taluk. An approximate estimate of quantities is given overleaf. These quantities are not guaranteed. The work should be completed by the end of May 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given overleaf, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees three hundred (Rs. 300) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring and improving Kambliganahalli Agraharadakere Minor Tank Registered No. 15 of Hoskote Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Approximate quantities required for restoring and improving Kambliganahalli Agrahardakere Minor Tank Register No. 154 of Hoskote Taluk.

No.	Items of work	Unit	Quantity	Rate	Rates in Figures	Rates in Words
				Rs. a. p.		
	Bund.					
1	Earthwork cutting grips	Grade	23	2 0 0		
2	Clearing jungle with roots	,,	23	2 0 0		
3	Earthwork to bund with watering and tamping	C.yd.	3,374	0 3 6		
4	Conveying and consolidating the earth available from draft and approach clearing	,,	2,570	0 1 0		
5	Turfing the slopes of bund with watering till it is satisfactory	S.yd.	4,714	0 1 0		
6	New stone revetment	C.yd.	519	1 12 0		
7	Resetting old revetment with new jelly	,,	120	1 0 0		
8	Providing and fixing new grade stones with bed slabs including figures chiseled and painted	Each	24	2 0 0		
9	Do Gauge stones do ..	,,	1	10 0 0		
10	Do Register No. stones do ..	,,	1	4 0 0		
11	Do B. M. stones	,,	2	3 0 0		
12	Do Index stones do ..	,,	24	0 8 0		
	Waste Weir.					
1	Earthwork excavation foundation of waste weir draft and approach clearing	C.yd.	3,465	0 2 6		
2	Stone jelly concrete in surki mortar ..	C.ft.	353	0 3 9		
3	Burnt stone slabs 6″ thick dressed and fixed in surki mortar	S.ft.	384	0 6 0		
4	Burnt brick in surki mortar ..	C.ft.	315	0 4 9		
5	Surki mortar plastering	Sqr.	1·00	4 0 0		
6	Rough stone work old with new jelly .	C.yd.	67	0 14 0		
	Right and Left sluices.					
1	Earthwork out opening the bund and refilling with watering and tamping after constructing sluice	C.yd.	32	0 5 0		
2	Burnt stone jelly concrete in surki mortar	C.ft.	188	0 3 9		
3	Burnt brick in surki mortar ..	,,	392	0 4 9		
4	Burnt stone slabs 6″ thick dressed and fixed in surki mortar	S.ft.	184	0 6 0		
5	Cutting holes in slabs for orifice and guide slab	Each	6	1 0 0		
6	Carting and fixing 6″ C. I. pipes (pipes will be supplied departmentally at Bangalore)	R.ft.	72	..		
7	Surki mortar plastering	Sqr.	4·46	4 0 0		
8	Providing and fixing 1¼″ dia. rod with looking arrangements.	Each	2	16 0 0		

Notification dated 10th April 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to (2 P.M.) on 25th April 1936 for restoring the breached Averahalli tank Registered No. 118 of Channapatna Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1936.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees four hundred only (Rs. 400) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring the breached Averahalli tank, Registered No. 118 of Channapatna Taluk, in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Approximate quantities required for restoring the Breached Averahalli Tank, Registered No. 118 of Channapatna Taluk.

No.	Items of work	Unit	Quantity	Rate sanctioned	Rate quoted in	
					Figures	Words
	Bund.			Rs. a. p.		
1	Clearing jungle and cutting grips ..	Grade	18	2 0 0		
2	Earthwork to bund with lead and lift, including watering and tamping ..	C.yd.	6,530	0 4 0		
3	Lead and consolidation charges for the earth available from the draft and approach clearing of waste weir ..	,,	767	0 1 6		
4	Rough stone work new with 2½ miles lead	,,	1,013	2 0 0		
5	Removing and resetting old stone work with new jelly	,,	295	1 0 0		
6	Puddle work in the breach ..	,,	227	0 12 0		
7	Removing silt in the breach ..	,,	151	0 2 6		
8	Turfing the slopes of bund and watering till it is satisfactory	S.yd.	4,603	0 1 0		

No.	Items of work	Unit	Quantity	Rate sanctioned	Rate quoted in Figures	Rate quoted in Words
				Rs. a. p.		
9	Providing and fixing new grade stones with bed slabs including figures chiseled and painted	Each	18	2 0 0		
10	Do B. M. stones painted ..	,,	2	3 0 0		
11	Do Register No. and date stone painted.	,,	1	3 0 0		
12						
13	Do New gauge stone	,,	1	14 0 0		
	Do Index stones	,,	18	0 6 0		
	Sluice.					
1	Earthwork cut opening the bund and refilling with consolidation after completing the sluice work ..	C.yd.	58	0 6 0		
2	Earthwork excavating foundation ..	,,	13	0 4 0		
3	Burnt stone jelly concrete in surki mortar	C.ft.	127	0 4 3		
4	Burnt brick in surki mortar ..	,,	575	0 5 0		
5	Burnt stone slabs 6″ thick dressed and fixed in surki mortar	S.ft.	157	0 6 0		
6	Plastering with surki mortar ..	Sqr.	5·25	4 0 0		
7	Pointing with cement	,,	0·57	4 0 0		
8	Cutting in platform and guide stones..	Each	2	0 8 0		
9	Rough stone work new with 2½ miles lead	C.yd.	6	2 0 0		
10	Providing wooden plug with iron rod and locking arrangements ..	Each	1	19 0 0		
	Waste Weir.					
1	Earthwork excavation draft and approach clearing in gravelly soil ..	C.yd.	1,151	0 4 0		
2	Do for foundation	,,	129	0 4 0		
3	Burnt brick in surki mortar ..	C.ft.	1,493	0 5 0		
4	Burnt stone slabs 6″ thick dressed and fixed in surki mortar	S.ft.	391	0 6 0		
5	Plastering with surki mortar ..	Sqr.	22·08	4 0 0		
6	Cutting joggle joints	Each	39	1 0 0		
7	Rough stone apron new with the required jelly with 2½ miles lead ..	C.yd.	92	2 0 0		

Notification, dated 11th April 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 25th April 1936 for restoring Haldenhally Hongekere, R. No. 105, of Anekal Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. and 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred and fifty in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Haldenhally Hongekere, R. No. 105, of Anekal Taluk," in default of which tenders will be rejected.

5. The final acceptance of any of tender will rest with the Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10 Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Approximate quantities required for restoring Haldenhalli Hongekere, Registered No. 105 of Anekal Taluk.

No.	Items of work	Unit	Quantity	Rate	Rates in	
					Figures	Words
				Rs. a. p.		
	Bund.					
1	Earthwork cutting grips	Grade	16	1 8 0		
2	Earthwork to bund with watering and tamping	C.yd.	7,000	0 3 3		
3	Turfing to slopes of bund and watering till it is satisfactory	S.yd.	6,162	0 0 10		
4	Providing and fixing Index stones ..	Each	17	0 4 0		
5	Removing and refixing old grade stones with figuring and painting ..	,,	14	0 8 0		
6	Do B. M. stones do ..	,,	2	0 8 0		
7	Do Register No. stones do ..	,,	1	1 0 0		
8	Providing and fixing new grade stones with bed slabs including figures chiseled and painted	,,	3	2 0 0		
9	Do gauge stones do ..	,,	1	12 0 0		
10	New stone revetment	C.yd.	913	1 10 0		
11	Earthwork excavating trench along front toe to fill in good clay and gravel	,,	854	0 3 0		
12	Filling the trench with good clay and gravel puddle	,,	854	0 6 0		
	Sluice.					
1	Earthwork cut opening the bund and refilling with consolidation after repairs to sluice	,,	50	0 5 0		
2	Stone jelly concrete in surki mortar ..	C.ft.	10	0 3 3		
3	Burnt brick in surki mortar ..	,,	20	0 5 0		
4	Burnt stone slabs 6″ thick dressed and fixed in surki mortar	S.ft.	10	0 6 0		
5	Plastering with surki mortar ..	Sqr.	10·00	4 0 0		
6	Providing plug and rod 1¼″ dia. with locking arrangements	Each	1	14 0 0		

No.	Items of work	Unit	Quantity	Rate	Rates in Figures	Rates in Words
	Waste Weir.			Rs. a. p.		
1	Earthwork excavating foundation ..	C.yd.	4	0 3 0		
2	Removing and refixing burnt stone slabs in surki mortar	C.ft.	74	0 1 6		
3	Burnt brick in surki mortar ..	,,	328	0 5 0		
4	Plastering with surki mortar ..	Sqr.	4.27	4 0 0		
5	Stone jelly concrete in surki mortar with plastering	C.ft.	222	0 4 6		
6	Removing and resetting old apron with new jelly	C.yd.	50	0 14 0		
7	Earthwork to training bank with watering and tamping	,,	119	0 3 3		
8	Rough stone work new with lead etc ..	,,	18	1 10 0		

Notification dated 11th April 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M., on 25th April 1936, for improving Gollahalli Ramegowdankere Minor Tank Register No. 78 of Anekal Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1936.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

4. Each tender must be accompanied by a deposit of Rupees one hundred and fifty in cash or Government Promissory Notes, as earnest money, and be superscribed " Tender for Improving Gollahalli Ramegowdankere Minor Tank Register No. 78 of Anekal Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond ; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office, in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8 On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10 Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for Contractor's profit.

11 In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Approximate quantities required for Improving Gollahalli Ramegowdankere Minor Tank Register No. 78 of Anekal Taluk.

No.	Items of work	Unit	Quantity	Rate sanctioned	Rate quoted in Figures	Rate quoted in Words
				Rs. a. p.		
	BUND.					
1	Clearing Jungle and cutting grips ..	Grade	10	2 0 0		
2	Earthwork to bund with lead and lift including watering and tamping ..	C.yd.	4,015	0 3 6		
3	Rough stone revetment, new ..	,,	283	2 0 0		
4	Resetting old stone work with new Jelly	,,	75	1 0 0		
5	Turfing the slopes of bund and watering till it is satisfactory	S.yd.	2,594	0 1 0		
6	Providing and fixing new grade stones with bed slabs including figures chistled and painted	Each	10	2 0 0		
7	Do B. M. stones.....do ..	,,	2	3 0 0		
8	Do Register No. and date stone do	,,	1	4 0 0		
9	Do Gauge stone do ..	,,	1	15 0 0		
	WASTE WEIR.					
1	Earthwork excavating foundation to bodywall, draft and approach clearing and using the earth to training bank with consolidation	C.yd.	78	0 3 0		
2	Burnt brick in surki mortar ..	C.ft.	481	0 5 0		
3	Plastering with surki mortar ..	Sqr.	7.00	3 12 0		
4	Burnt stone slabs 6″ thick, dressed and fixed in surki mortar	S.ft.	85	0 6 0		
5	Removing and refixing the coping slab in surki mortar	,,	26	0 2 0		
6	Burnt stone jelly concrete in surki mortar	C.ft.	132	0 4 0		

M. A. SRINIVASACHARI,
Executive Engineer.

MYSORE DIVISION.

Abstract Notification dated 5th April 1936.

The attention of the public is invited to the detailed Notification, calling for Tenders for Urgent Improvements to Malleswaraswamy's temple at Krishnarajpet in pages 497 to 498, Part VI of the *Mysore Gazette*, dated 9th April 1936.

The last date of receipt of tender is 20th April 1936.

Abstract Notification dated 5th April 1936.

The attention of the public is invited to the detailed notification, calling for tenders for construction of a Causeway across Mugur Addahalla on T.-Narsipur-Chamarajanagar Road, in pages 499 to 500, Part VI of the *Mysore Gazette*, dated 9th April 1936.

The last date of receipt of tender is 27th April 1936.

V. V. PATANKAR,
Executive Engineer.